

New Water Supply Distribution System Anaconda Civilian Conservation Center

OWNER: US Dept. of Labor (Job Corps. Division)

CONTRACT: \$1,200,000

DATES: 6/15/10 - 12/31/11

ENGINEERING: DOWL HKM, RICHARD TALLEY, 406-723-8213

SUBCONTRACTORS:

None

SCOPE OF WORK: Work included, but not limited to,

- Clearing and grubbing
- Install BMP's
- Excavate and remove 6,000' of 4" & 6" water mains, 17 fire hydrants, and 2,000' of water service line
- Remove existing curb stops
- Install 580' of 8" water main
- Install 4,500' of 6" water main
- Install all gate valves, elbows, and tees
- Install new fire hydrant assembly (17)
- Install 2000' of 1" to 1 ¼" water service line
- Install numerous curb stops and service saddles
- Modify plumbing in dorms and other buildings
- Connect to existing water main storage tanks
- Construct underground utility crossings
- Reconstruct and pave road
- Restore sidewalks
- Perform traffic control
- Perform disinfection/leakage testing
- Reclaim construction area